

New word (新单词)

- ◆ scaffold
- ◆ vendor (supplier)
- ◆ overhead space
- ◆ concrete
- ◆ jumper
- ◆ babbitt
- ◆ chain hoist
- ◆ glove
- ◆ jobsite (site)
- ◆ 脚手架
- ◆ 供应商
- ◆ 顶层空间
- ◆ 混凝土的
- ◆ 跳线
- ◆ 巴氏合金
- ◆ 手动葫芦
- ◆ 手套
- ◆ (工作)现场

New word (新单词)

- ◆ travel
- ◆ fire extinguisher
- ◆ lifeline
- ◆ paramount
- ◆ fatigue
- ◆ key ring
- ◆ inhibit
- ◆ 行程
- ◆ 灭火器
- ◆ 救生索
- ◆ 最重要的
- ◆ 疲劳
- ◆ 钥匙圈
- ◆ 抑制

Elevator Installation 电梯安装

- Before installing an elevator,应该做哪些准备工作?
 - 研究图纸 studying drawing
 - 准备工具 preparing equipment
 - 总体确认 General Verification

Elevator Installation 电梯安装

- When **installing** a new elevator, **installers** begin by studying blueprints to determine the equipment needed.
- 在安装一部新的电梯之前，安装者应该先研究图纸以确定所需的设备。

Section1 Elevator Installation 电梯安装

Delivery of material 物料交付

- **Compare** all components in the shipment **against** the shipping list to check if there is any shortage.
- 根据发运清单核对所有运货部件，以确认是否存在少料。

Section1 Elevator Installation 电梯安装

Installation Schedule 安装进度

- **The time** taken to install these units will **vary** from project to project and will be **dependent upon** the following factors.
- 安装时间随项目的不同而不同，取决于以下因素。

Section1 Elevator Installation 电梯安装

Installation Schedule 安装进度

- The number of floors served.

服务楼层数目

- The site conditions and the experience of the installing team.

场地条件和安装队的经验

Section1 Elevator Installation 电梯安装

Installation Schedule 安装进度

- **It is very important** that supervisors visit the site to verify all dimensions are correct and all services are available before the installing crew commences.
- 在安装队开工前，管理人员视察现场以确认尺寸正确和所有服务设施齐全是非常重要的。

2 Safety During Installation 装梯安全

General safety Caution 总体安全注意事项

Handle with circuit 电路操作

Labor Insurance Protection 劳保防护

Ladders 梯子

False Cars 仿形轿厢

2 Safety During Installation 装梯安全

Fall Protection 坠落防护

Chain Hoist 手拉葫芦

Gas Tanks 气罐

Precautions for Welding 焊接防护措施

Rope Fastening 钢丝绳紧固

2 Safety During Installation 装梯安全

- Safety is everyone's responsibility.

安全是每个人的责任。

- Do not hesitate to caution anyone performing an unsafe act.

应及时提醒有不安全行为的人。

- Likewise accept such caution from others with a spirit of thanks.

同样，以感激的心情接受别人的提醒。

2 Safety During Installation 装梯安全

- Continuous review Employees ‘ Safety Handbook, company safety policy and procedures, specific jobsite requirements

持续地翻阅电梯行业员工安全手册、公司的安全政策与程序、以及工作现场要求。

2 Safety During Installation 装梯安全

- Place a sticker in the controller near the inspection switch that reads as follows:
"GATE OR SAFETY CIRCUITS SHALL NEVER BE JUMPED OUT."

在控制器检修开关旁放一块标牌，内容如下：
出入口及安全回路不得短接。

以上内容仅为本文档的试下载部分，为可阅读页数的一半内容。如要下载或阅读全文，
请访问：<https://d.book118.com/126030201012011003>